

1050142

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW NE NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,921-0000
990 feet from N/SX section line
1650 feet from W/EX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Elaine Well # 2-24

Operator: Gear Petroleum Co., Inc.

County Lane

Name & Address 300 Sutton Place

Well Total Depth 4640 150.80 feet

Address Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Company License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 3:00 am Day: 13 Month: February Year: 19 84

Plugging proposal received from Marion Burriss

(company name) Warrior (phone) 316-653-7716

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2230' with 50 sx cement

2nd plug at 1100 with 50 sx cement

3rd plug at 380' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 10 sx cement, 7th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:00 am Day: 13 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2230' with 50 sx cement, 2nd plug at 1100' with

50 sx cement, 3rd plug at 380' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th & 7th plugs to circulate rathole

and mousehole with 10 sx cement each.

RECEIVED
STATE CORPORATION COMMISSION
2-15-84
FEB 15 1984

Remarks: Use 60/40 Pozmix with 2% gel 3% cc. by Allied
(If additional description is necessary, use BACK of this form.)
Wichita, Kansas

I (not) observe this plugging.
DATE 2-13-84

INV. NO. 0336
2-13

Signed Richard W. Lacey
(TECHNICIAN)