

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-02215-00-00
Spot: SENWSWNE Sec/Twnshp/Rge: 13-21S-20E
3525 feet from S Section Line, 2106 feet from E Section Line
Lease Name: EWING B Well #: V-12X
County: ANDERSON Total Vertical Depth: 660

Operator License No.: 34170
Op Name: SIRIUS ENERGY CORP.
Address: 526 COUNTRY PL, SOUTH
ABILENE, TX 79606

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	650		0 SX
SURF	12	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2012 12:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: RANDY TETER Company: _____ Phone: (785) 448-8571

Proposed Plugging Method: Run 3/4 inch pipe approx. 660 feet and fill 2 inch pipe with approx. 20 sacks. Run 1 inch pipe to bottom and fill backside to surface with approx. 100 sacks.

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE
Date/Time Plugging Completed: 07/18/2012 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 3/4 INCH INSIDE 2 INCH CASING TO 567 FEET AND FILL WITH 12 SACKS OF PORTLAND CEMENT TO SURFACE. RUN 1 INCH OUTSIDE TO 250 FEET AND PUMP 90 SACKS OF CEMENT. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 102 SACKS OF CEMENT.

Perfs:

Remarks:

Plugged through: TBG

RECEIVED
SEP 14 2012
KCC Chanute Dist. #3
LS

RECEIVED
SEP 19 2012

KCC WICHITA

District: 03

Signed L. Short (TECHNICIAN)
12/10/12