

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21074
Spot: SESE Sec/Twnshp/Rge: 10-29S-18W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: CORLEY Well #: 1
County: KIOWA Total Vertical Depth: 4981 feet

Operator License No.: 3959
Op Name: SIROKY OIL MANAGEMENT
Address: PO BOX 464
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3417		WITH 2 SX CMT
CIBP		4798		
PROD	4.5	4979	2002	WITH 450 SX CMT
SURF	8.625	521		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/12/2012 9:00 AM
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC
Proposal Rcvd. from: BRIAN SIROKY Company: SIROKY OIL MANAGEMENT Phone: (620) 770-0621

Proposed Plugging Method: SAND TO 50' ABOVE PERFS. PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. PLUG AT 530' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/12/2012 1:00 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

SET CIBP @ 3417' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1205' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 530' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3529	3532		

RECEIVED
SEP 20 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
SEP 14 2012
KCC DODGE CITY

Signed

Daniel Bernasconi
12/12/12
(TECHNICIAN)

AMY