

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23525-00-00
Spot: NWSESE Sec/Twnshp/Rge: 18-7S-23W
380 feet from S Section Line, 610 feet from E Section Line
Lease Name: FOUNTAIN Well #: 1-18
County: GRAHAM Total Vertical Depth: 3980 feet

Operator License No.: 32686
Op Name: REILLY OIL COMPANY, INC.
Address: PO BOX 277
WAKEENEY, KS 67672

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3830		
DVT		2172		250 SX CMT
PROD	5.5	3978		490 SX
SURF	8.625	221		165 SX
TI	2.875	3778		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/17/2012 9:00 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: MYRON WOODY Company: WW DRILLING Phone: (785) 743-6774

Proposed Plugging Method: DV tool @ 2172' w/250 sx.
Perforations @ 3847' to 3849' and 3764' to 3766'.
Ordered 425 sx 60/40 pozmix 4% gel cement w/400 # hulls and 13 sx gel.
CIBP @ 3830'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/17/2012 4:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3785'. Pumped 50 sx cement w/200 # hulls.
Pulled tubing to 3282'. Pumped 11 sx gel.
Pulled tubing to 2186'. Pumped 130 sx cement.
Pulled tubing to 1187'. Pumped 180 sx cement. Good circulation of cement.
Pulled tubing out. Topped off w/15 sx cement.
Tied on to back side. Squeezed w/12 1/2 sx cement. Shut in w/300 psi.

Perfs:

Top	Bot	Thru	Comments
3847	3849		
3764	3766		

RECEIVED
SEP 24 2012
KCC WICHITA

Remarks: SOS CEMENT TICKET # 615

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

SEP 18 2012