

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-25447-00-00  
Spot: S2N2NW Sec/Twnshp/Rge: 18-20S-21W  
990 feet from N Section Line, 1320 feet from W Section Line  
Lease Name: MAIER "A" Well #: 1-18  
County: NESS Total Vertical Depth: 4378 feet

Operator License No.: 34579  
Op Name: COBALT ENERGY LLC  
Address: 115 S. BELMONT #12 PO BOX 8037  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	225		WITH 135 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/25/2012 2:00 PM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: BILL SANDERS Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: 1ST PLUG AT 1440' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: DANIEL BERNASCONI Witness Type: NONE  
Date/Time Plugging Completed: 09/25/2012 4:00 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

1ST PLUG AT 1440' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

RECEIVED  
OCT 09 2012  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

Signed: Daniel Bernasconi  
10/16/12 (TECHNICIAN)