

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22246-00-00
Spot: NENENW Sec/Twnshp/Rge: 21-30S-10W
330 feet from N Section Line, 2310 feet from W Section Line
Lease Name: O'MOORE Well #: 1
County: KINGMAN Total Vertical Depth: 4850 feet

Operator License No.: 3372
Op Name: DIXON ENERGY, INC.
Address: 8100 E 22ND N BLDG 300, STE 200
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4600		
PROD	5.5	4832		150 SX
SURF	8.625	264		200 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/14/2012 8:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: PJ DIXON Company: _____ Phone: (316) 264-9632

Proposed Plugging Method: Per KCC rules and Regulations

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/14/2012 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 4348' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2757' PULLED CASING. RAN TUBING INTO 1669' SPOTTED 35 SX CEMENT, PULLED TUBING TO 1150' SPOTTED 35 SX CEMENT. PULLED TUBING TO 320' CIRCULATED TO SURFACE WITH 80 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4731	4734		
4656	4660		
4319	4450		

RECEIVED
OCT 10 2012
KCC WICHITA

Remarks: BASIC ENERGY DID CEMENTING WITH, 60/40 4% POS MIX, TICKET #6685.

Plugged through: TBG

District: 02

Signed BJ Hope
10/16/12 (TECHNICIAN)