

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

** OK TO PLUG AS PLUG PT. IS WITHIN 5 YR. CUTOFF.*
API Well Number: 15-001-27506-00-00
Spot: NENESWSE Sec/Twnshp/Rge: 3-26S-18E
1155 feet from S Section Line, 1485 feet from E Section Line
Lease Name: N FINNEY Well #: 34
County: ALLEN Total Vertical Depth: ██████████

Operator License No.: 33221
Op Name: ROXANNA PIPELINE, INC.
Address: 4600 GREENVILLE AVE STE 200
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	1005		
SURF	7	20		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/18/2008 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: TOM GILBERT Company: ROXANNA PIPELINE, INC. Phone: (214) 691-6216

Proposed Plugging Method: Well has 2 7/8" casing to approximately 1005' that was cemented in from bottom to top. The plugging proposal was to squeeze the 2 7/8" casing full of cement from top to bottom.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 01/18/2008 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

The pump truck was connected directly to the 2 7/8" casing. Cotton seed hulls were mixed with first of the cement that was to be pumped. Cement was pumped into the 2 7/8" casing until the well held pressure. The well was shut in at 500 psi. A total of 28 sacks of Portland cement was reported used to plug this well.

Perfs:

RECEIVED
OCT 10 2012
KCC Chanute Dist. #3
RD
RECEIVED
OCT 12 2012
KCC WICHITA

Remarks: THIS WELL WAS GPS'D AS NFI 43.

Plugged through: CSG

District: 03

Signed [Signature]
10/19/12 (TECHNICIAN)