

\* OK TO PLUG AS PLUG DT. IS WITHIN 5 YR. CUTOFF.

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-27583  
Spot: NWENWSE Sec/Twnshp/Rge: 3-26S-18E  
2493 feet from S Section Line, 1792 feet from E Section Line  
Lease Name: N FINNEY Well #: 73  
County: ALLEN Total Vertical Dep:                     

Operator License No.: 33221  
Op Name: ROXANNA PIPELINE, INC.  
Address: 4600 GREENVILLE AVE STE 200  
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	840		
SURF	7	20		

Well Type: OIL UIC Docket No:                      Date/Time to Plug: 01/21/2008 8:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: TOM GILBERT Company: ROXANNA PIPELINE, INC. Phone: (214) 691-6216

Proposed Plugging Method: Well has 2 7/8" casing to approximately 840' that was cemented in from bottom to top. The plugging proposal was to squeeze the 2 7/8" casing full of cement from top to bottom.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE  
Date/Time Plugging Completed: 01/21/2008 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report: The pump truck was connected directly to the 2 7/8" casing. Cotton seed hulls were mixed with first of the cement that was to be pumped. Cement was pumped into the 2 7/8" casing until the well held pressure. The well was shut in at 500 psi. A total of 29 sacks of portland cement was reported used to plug this well.

Perfs:   
  
  
  
  
  
  
  
  
  
RECEIVED  
OCT 10 2012  
KCC Chanute Dist #3  
RD  
RECEIVED  
OCT 12 2012  
KCC WICHITA

Remarks: THIS WELL WAS GPS'D AS NFI01.  
Plugged through: CSG

District: 03

Signed [Signature] (TECHNICIAN)