

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-06753-00-00
Spot: S2NESE Sec/Twnshp/Rge: 31-14S-13W
1650 feet from S Section Line, 660 feet from E Section Line
Lease Name: MILLER Well #: B-2
County: RUSSELL Total Vertical Depth: 3126 feet

Operator License No.: 5184
Op Name: SHIELDS OIL PRODUCERS INC.
Address: 326 N MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3124		150 SX
SURF	8.625	320		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/06/2012 9:30 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: MICHAEL MCGLOCKLIN Company: SHEILDS OIL PRODUCER, INC. Phone: (785) 483-3141

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls and 10 sx gel.
Re-ordered 200 sx 60/40 pozmix 4% gel cement.
Perforations: 1250', 630' and 250'.

Plugging Proposal Received By: RAY DINKEL Witness Type: NONE
Date/Time Plugging Completed: 09/06/2012 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2950'. Pumped 9 sx gel followed by 75 sx cement w/150 # hulls.
Pulled tubing to 1250'. Pumped 115 sx cement w/250 # hulls.
Cement circulated to surface.
POOH. Hooked on to casing and pumped 110 sx cement.
Cement circulated to surface through braden head. Shut in.

Perfs:

RECEIVED
SEP 14 2012
KCC WICHITA

Remarks: ALLIED CEMENTING, INC. TICKET # 56606

Plugged through: TBG

District: 04

Signed Ray Dinkel
09/10/12 (TECHNICIAN)

CM

SEP 10 2012