

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10153-00-03
Spot: SENWNE Sec/Twnshp/Rge: 36-32S-42W
4668 feet from S Section Line, 798 feet from E Section Line
Lease Name: GRACE RICORD Well #: 1-36
County: MORTON Total Vertical Depth: 5600 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN LLC
Address: 15 E 5TH ST STE 3200
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3080		
L1	4.5	3354	1000	WITH 925 SX CMT
PROD	5.5	1075		WITH 195 SX CMT
SURF	8.625	1472		WITH 750 SX CMT

Handwritten signature

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/18/2012 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed
Plugging
Method:

CUT TB GOFF BELOW 1500'. PUMP 20 SX CMT AT 1500'. SHOOT CASING OFF BELOW 500'. CIRCULATE CMT FROM 500' TO 0'. CHECK 5 1/2" X 8 5/8" ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/21/2012 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TUBING FISH TOP @ 1732'. PUMP 20 SX CMT AT 1500'. TAG CMT AT 1678'.
PUMPED ANOTHER 20 SX CMT AT 1500'. TAGGED CMT AT 1133'. PUMPED 70 SX
CMT DOWN 5 1/2". TAGGED AT 530'. TOPPED OFF WITH 57 SX CMT & PRESSURED
TO 300#. VISUALLY CHECKED 8 5/8" X 5 1/2" ANNULUS. IT WAS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
3166	3172		
3138	3141		
3092	3172		
2878	2889		
1125	1150		
1100	1150		

RECEIVED
OCT 15 2012
KCC WICHITA

Remarks: USED PORTLAND COMMON BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED

OCT - 1 2012

KCC DODGE CITY

Signed

Handwritten signature of Ken Jehlik
10/19/12

(TECHNICIAN)

Handwritten initials