

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-27688-00-00  
Spot: SWNWNESE Sec/Twnshp/Rge: 9-24S-16E  
2145 feet from S Section Line, 1155 feet from E Section Line  
Lease Name: GLADES Well #: V-16  
County: WOODSON Total Vertical Depth: 10 SX

Operator License No.: 5556  
Op Name: VIVA INTERNATIONAL, INC.  
Address: 8357 MELROSE DR  
LENEXA, KS 66214

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	41		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/03/2011 12:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: TIM WEST Company: VIVA INTERNATIONAL, INC. Phone: (620) 365-0457

Proposed Pumping Method: Pump cement through the drill stem and place a 50' cement plug at TD and 425'. Circulate cement from 300' to surface.

Plugging Proposal Received By: RYAN DULING Witness Type: NONE  
Date/Time Plugging Completed: 05/03/2011 12:00 PM KCC Agent: RYAN DULING

Actual Plugging Report:

Mix and pumped gel down the Drill stem at TD. Pumped 20 sacks of cement through the drill stem at TD. Pull drill stem to 425'. Pumped 10 sacks of cement through the drill stem at 425'. Pulled drill stem to 300'. Pumped and circulated cement through the drill stem from 300' to surface. Pulled the rest of the drill stem and topped the well off with cement. A total of 70 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED  
OCT 10 2012  
KCC Chanute Dist #3

RD

RECEIVED  
OCT 12 2012

KCC WICHITA

Remarks:

Plugged through: DP

District: 03

Signed [Signature]  
10/10/12 (TECHNICIAN)