

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26378-00-00
Spot: SWSENE Sec/Twnshp/Rge: 32-14S-17W
1150 feet from N Section Line, 600 feet from E Section Line
Lease Name: LEIKER Well #: 1-32
County: ELLIS Total Vertical Depth: 3590 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	984		400 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/11/2012 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo-seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE
Date/Time Plugging Completed: 09/11/2012 7:15 AM KCC Agent: DAVID WANN

Actual Plugging Report:

1st plug @3475 w/25 sx
2nd plug @1100 w/75 sx
3rd plug @500 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx


Perfs:

Remarks: QUALITY

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED
OCT 12 2012
KCC WICHITA

OCT 06 2012