

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-26377-00-00  
Spot: NENWSENE Sec/Twnshp/Rge: 35-14S-18W  
1625 feet from N Section Line, 900 feet from E Section Line  
Lease Name: KOIRTH Well #: 1-35  
County: ELLIS Total Vertical Depth: 3730 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1515 WYNKOOP, STE 700  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1060	0	450 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/18/2012 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 195 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 09/18/2012 11:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @3608 w/25 sx  
2nd plug @1250 w/25 sx  
3rd plug @1100 w/100 sx  
4th plug @525 w/40 sx  
5th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

RECEIVED  
OCT 12 2012  
KCC WICHITA

District: 04

Signed Cory Morris  
10/22/12 (TECHNICIAN)

OCT 06 2012