

Date 11-4-03

- New Situation
- Response to Request
- Follow-up

Operator Ritchie Expl Inc # 4767

1750' FML
1120' FEL

Address Box 783189

Location W/2-NW-SE-NE, Sec 32, T 16 S, R-30W

Wichita, KS 67278

Lease Stewart Well # 32A

Phone No. _____

County Lane

Oper. _____ Other _____

Reason for Investigation: AIT # completion. 15-101-21, 821

1400' usable water.

GPS Reading 38.62295° N 100.65496° W Elev 2877'

Problem: _____

RECEIVED

DEC 04 2003

KCC WICHITA

Person(s) Contacted: Prod. Forman Pete

ASCO oil tools on hole to open portcollar.

Findings: Port collar @ 2243', Allied cementing on location w/

450 sx 60/40 poz 6% gel w/ 1/4 # flow seal.

Opened portcollar had blow started cmt had circulation + lost it w/ 150 sx in. pumped 150 sx more shut down 30min pumped approx 50 sx + got good returns to pit didn't see any cmt @ surface. displaced cmt in tubing shut portcollar + pressured up.

11-5-03 EKI can Temp log starting @ 10:15 photos taken: _____

Action/Recommendations: On location @ 11:00 am

off @ 2:30 pm

10-18-03 - pump 30 sx down annulus Temp survey - TOC @ 575'
work not completed.

- Lease Inspection
- Complaint
- Field Report

alt. II complete

By Kevin D Strube
Kevin D Strub

S.D.
12-1-03