

STATE OF KANSAS

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67702

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-071-20196 - 0000

Lease Name Edsall E

WELL NUMBER 4

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 11 TWP. 16S RGE. 43W (E) or (W)

COUNTY Greeley

Date well completed 4/26/80

Plugging Commenced 10/18/99

Plugging completed 10/19/99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Herman L. Loeb

Address P. O. Box 524 Lawrenceville, IL 62439

Phone (618) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/25/99 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, IS well log attached? _____

Producing Formation Morrow Depth to Top 5140' Bottom 5158' T.D. 5255'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Oil</u>	<u>5140'</u>	<u>5158'</u>	<u>8 5/8"</u>	<u>482'</u>	<u>0'</u>
				<u>5 1/2"</u>	<u>5255'</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Set CIBP @ 5090', spot 2 sk cement on plug. Run cement bond log. Set CIBP @ 2000', perforate @ 1950'. RIH w/ tubing to 1950'. RU Allied Cementing, pump 180 sk cement down tubing, cement circulates to surface. Pull tubing to 600', pump 20 sk cement, circulates to surface. POH w/ tubing. Hook on to 5 1/2" casing, pump 10 sk cement, pressure to 800 psi. Hook on to 8 5/8" surface casing, pump 100 sk down annulus. All cement 60/40 pozmix w/ 6% gel.

Name of Plugging Contractor Mull Drilling License No. 5144

Address P O Box 2758 Wichita, KS 67201-2758

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb

STATE OF Illinois COUNTY OF Lawrence '33.

George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God. (Signature) George A. Payne

(Address) 7588 Marywood Drive Newburgh, IN 47630

Subscribed and sworn to before me this 28th day of October, 19 99

Donna Carlene Lucas
Notary Public

My commission expires: April 6, 2002

RECEIVED
STATE CORPORATION COMMISSION
11-1-99
NOV - 1 1999

"OFFICIAL SEAL"
DONNA CARLENE LUCAS
Notary Public, State of Illinois
My Commission Expires: 4/6/02

Form CP-4
R