

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Greeley

County. Sec. 11 Twp. 16S Rge. (E) 43 (W)

Location as "NE/CNW/SW" or footage from lines NE NE SE

Lease Owner C. R. Associates

Lease Name Evans Well No. 1

Office Address 602 Rule Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 25 1969

Application for plugging filed April 24 1969

Application for plugging approved April 24 1969

Plugging commenced April 24 1969

Plugging completed April 25 1969

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & Shale		0	359	8 5/8	359	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 100 sacks cement from 1600' to 1300'; spotted 25 sacks cement at 350'; spotted 10 sacks cement from 40' to 0' by Halliburton pump truck through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION
5-13-69
MAY 13 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rine Drilling Company, Inc.

Address Suite 600 - 300 West Douglas, Wichita, Kansas 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Richard G. Smith, agent of (employee of owner) or (owner's operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard G. Smith
Richard G. Smith, Agent
602 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April, 1969

Celia A. Smith
Celia A. Smith Notary Public.



10-8-72

copy for KSCC
15-071-20606-0000

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1969
CONSERVATION DIVISION
Wichita, Kansas

NE NE SE
SECTION 11-16S-43W
GREELEY COUNTY, KANSAS

EVANS WELL NO. 1

CONTRACTOR: RINE DRILLING COMPANY, INC.

STARTED: APRIL 11, 1969

COMPLETED: APRIL 25, 1969

LOG

Sand & Shale	0' - 792'	Totco - 1/4° @ 359'. Run 9 jts. 85/8' cement w/260 sx. common + 3% cc cement through 1" w/100-sx.-common.
Shale	792' - 2590'	Totco - 3/4° @ 1946'
Red Bed, Shale & Anhydrite	2590' - 2735'	Totco - 1° @ 2735'
Shale, Red Bed	2735' - 3300'	Totco - 1° @ 3300'
Lime	3300' - 3600'	Totco - 1 1/4° @ 3600'
Lime & Shale	3600' - 4246'	
Gray Shale	4246' - 4378'	
Lime & Shale	4378' - 4496'	
Sandy, Lime & Shale	4496' - 4612'	
Lime & Shale	4612' - 5005'	Totco - 1 1/4° @ 4683'
Shale	5005' - 5100'	
Shale & Lime	5100' - 5251'	Totco - 1/2° @ 5251'
Lime	5251' - 5327'	
Shale	5327' - 5571'	TD - Plug from 1300'-1600' w/100 sx. com. + 4% gel. Plug @ 350' w/25sx. com. + 4% gel. Plug from 0' to 40' w/10 sx. common.

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss

I, R. M. Green, do hereby certify that the above is a true and accurate log of the Evans Well No. 1 located NE of NE of SE of Section 11-16N-43W, Greeley County, Kansas.

R. M. Green
R. M. Green, Secretary-Treasurer

Subscribed and sworn to before me this 29th day of April, 1969.



Bette J. Edwards
Bette J. Edwards, Notary Public

My Commission Expires: 6/8/70