

STATE OF KANSAS

STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67702

WELL PLUGGING RECORD

K.A.R. -82-3-117

API NUMBER 15-071-20267 •0000

Lease Name Evans E

WELL NUMBER 4

2310 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 11 TWP. 16S RGE. 43W ( E ) or ( W )

COUNTY Greeley

Date well completed 5/15/82

Plugging Commenced 10/18/99

Plugging completed 10/18/99

LEASE OPERATOR Herman L. Loeb

Address P. O. Box 524 Lawrenceville, IL 62439

Phone ( 618 ) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/25/99 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, IS well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 5148' Bottom 5167' T.D. 5362'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>0:1</u>	<u>5148</u>	<u>5167</u>	<u>8 5/8"</u>	<u>723'</u>	<u>0'</u>
				<u>4 1/2"</u>	<u>5362'</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Tubing hung up, run free point, cut tubing off @ 4900', POH w/ tbg. Set CIBP @ 4900', spot 2 sk cement on top. Set CIBP @ 2000'. Run cement bond log, perforate @ 720'. Hook on to 4 1/2" casing, pump 220 sk 60/40 pozmix w/ 6% gel, circulate cement back to the surface.

Name of Plugging Contractor Mull Drilling License No. 5144

Address P O Box 2758 Wichita, KS 67201-2758

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb

STATE OF Illinois COUNTY OF Lawrence '33.

George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God. (Signature) George A. Payne

(Address) 7588 Marywood Drive Newburgh, IN 47630

Subscribed and sworn to before me this 28th day of October, 19 99

Donna Carlene Lucas  
Notary Public

My commission expires: April 6, 2002

RECEIVED  
STATE CORPORATION COMMISSION  
11-1-99  
NOV - 1 1999

"OFFICIAL SEAL"  
DONNA CARLENE LUCAS  
Notary Public, State of Illinois  
My Commission Expires: 4/6/02

Form CP-4