

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67702

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-071-20163 - 0000

Lease Name Evans E

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line

380 Ft. from E Section Line

SEC. 11 TWP. 16S RGE. 43W (E) or (W)

COUNTY Greeley

Date well completed 3/10/79

Plugging Commenced 7/12/99

Plugging completed 7/12/99

LEASE OPERATOR Herman L. Loeb

Address P O Box 524 Lawrenceville, IL 62439

Phone (618) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 11, 1999 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, IS well log attached? _____

Producing Formation Morrow Depth to Top 5138' Bottom 5162' T.D. 5350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Oil</u>	<u>5138</u>	<u>5162</u>	<u>8 5/8</u>	<u>578'</u>	<u>0</u>
					<u>5329'</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, State the character of same and depth placed, from feet to feet each set. Set cast iron bridge plug @ 5100', spot 2 sk of cement on top of plug. Run tubing & packer to 2038', pressure test annulus above packer to 300 psi, holds ok. POH w/ tubing & packer. Run cement bond log, top of cement @ 2,380'. Set CIBP @ 2000'. Perforate @ 1950'. Run tubing to 1978'. Circulate cement back to surface. POH w/ tubing. Hook on to 5 1/2" casing, pump 55 sk cement, pressure to 500 psi, shut in casing. Hook on to surface casing, pump 100 sk, pressure to 100 psi. Shut in. Used 370 sk 60/40 pozmix w/ 6% gel.

Name of Plugging Contractor Key Rocky Mountain License No. 05866

Address P O Box 69 Cheyenne Wells, CO 80810

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb

STATE OF Illinois COUNTY OF Lawrence '33.


George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God. (Signature) George A. Payne

(Address) 7588 Marywood Drive Newburgh IN 47630

Subscribed and sworn to before me this 28 day of July, 19 99

Donna Carlene Lucas
Notary Public

My commission expires: 4-6-02



RECEIVED
STATE CORPORATION COMMISSION Form CP-4

AUG - 2 1999
8-2-99
CONSERVATION DIVISION
Wichita, Kansas

2