

STATE OF KANSAS
STATE CORPORATION COMMISSION
308 S. Market, Room 2078
Topeka, KS 67202

WELL PLUGGING RETURN
K.A.R.-82-3-117

API NUMBER 15-135-23,193-0000

LEASE NAME McCreight

WELL NUMBER #1

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 36 TWP. 20S RGE. 24W (K) or (W)

COUNTY Ness

Date Well Completed 1/30/87

Plugging Commenced 2/19/98

Plugging Completed 2/19/98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE# (785) 798-3641 OPERATORS LICENSE NO. 31627

Character of Well oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on 2/19/98 (date)

Mike Maier (KCC District Agent's Name).

ACO-1 filed? yes if not, is well log attached? attached to CP-1

Producing Formation Mississippian Depth to Top 4388 Bottom 4389 T.D. 4394

Give depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	720	---
				5.5	4394	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material used, state the character of same and depth placed, from feet to feet each set:

Mixed 50# of hulls & 20 sacks and spotted on bottom, 4392

Mixed 350# of hulls & 160 sacks and spotted at 1500'

Mixed 25 sacks and topped off the 5.5" casing

Mixed 5 sacks and pressured the backside to 500#

Name of Plugging Contractor Allied Cementing Co Inc License No.


Address P O Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Whitetail Crude, Inc

State of Kansas County of Ness, ss.

CONSERVATION DIVISION
Topeka, Kansas

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.



(Signature) Mike J. Fritzler

Mike J. Fritzler, President

(Address) P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 19 98

Debra Kerr
Debra Kerr Notary Public

My Commission Expires: 4/20/2001

USE ONLY ONE SIDE OF EACH FORM