


STATE OF KANSAS  
STATE CORPORATION COMMISSION

K-135-00KS-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Ness County, Sec. 15 Twp. 20 Rge. 24 (EX) (W)  
Location as "NE/CNW/SW" or footage from lines C NE SE SE  
Lease Owner Rupp-Ferguson Oil Co.  
Lease Name Pember Well No. 1  
Office Address 522 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 1-20-59 19  
Application for plugging filed 1-20-59 19  
Application for plugging approved 1-20-59 19  
Plugging commenced 1-20-59 19  
Plugging completed 1-20-59 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 4489 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	525	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 500, hulls-plug. Cement w/20 sacks through d.p. - mud to 40' - hulls-plug. Cement w/10 sacks. Drain up.

RECEIVED  
STATE CORPORATION  
JAN 27 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.  
Address 522 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
L. W. Knox (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. W. Knox*  
522 Petroleum Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 19 59



*Helen Horine*  
Notary Public.

PLUGGING  
FILE SEC. 15 T. 20 R. 24W  
BOOK PAGE 12 LINE 36

15.135.00150-0000

CONTRACTOR'S WELL LOG

Rupp-Ferguson No. 1 Pember  
NE SE SE, Sec. 15-20-24W,  
Ness County, Kansas

Elevation 2303 KB  
D & A  
Set 525' of 8 5/8" w/225 sax

Commenced: 1-7-59  
Completed: 1-20-59  
Contractor: Rupp-Ferguson Oil Co.

Figures Indicate Bottom of Formation

20 soil  
70 clay, shale & rock  
165 shale & clay  
190 sand  
250 shale & sand  
405 shale, red shale, sand  
471 sand & shale  
670 blue shale  
915 red bed  
930 Anhydrite  
1030 red bed  
1285 red sand  
1452 red bed  
1773 red bed, shale & shells  
2180 shale & shells  
3052 lime & shale  
3373 shale  
3845 lime & shale  
3959 lime  
4035 lime & shale  
4439 lime, chert & shale  
4449 Cong. shale  
4489 Miss. dolomite

STATE OF KANSAS)  
SEDGWICK COUNTY) SS:

I, L. W. Knox, Landman for Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Pember well.

JAN 27 1959  
CONSULTING DIVISION  
WELL LOGS DEPARTMENT

*L. W. Knox*  
L. W. Knox

Subscribed and sworn to before me this 22nd day of January, 1959.

*Helen Horine*  
Notary Public

My Commission Expires June 4, 1959.

PLUGGING  
FILE SEC. 15. T. 20. R. 24W  
BOOK PAGE 12 LINE 36

