

Kansas Corporation Comm.
Wichita State Office Bldg.
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

WELL NUMBER 135-23921 0000

LEASE NAME Lundy "A"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

3555 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 4 TWP. 20S RGE. 24 (X) or (W)

COUNTY Ness

Date Well Completed 2/13/96

Plugging Commenced 4:00AM 2/13/96

Plugging Completed 6:30AM 2/13/96

LEASE OPERATOR Black Diamond Oil, Inc.

ADDRESS P.O. Box 641 Hays, Kansas 67601

PHONE (913) 625-5891 OPERATORS LICENSE NO. 7076

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/12/96

by Richard Lacey

(KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No Log

Producing Formation None Depth to Top _____ Bottom T.D. 4434

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	218	8 5/8	218.03	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.

1st Plug @ 1640 w/50sks 15sks In Rat Hole Circulated 1st Plug 15minutes w/51 Vis Mud
2nd Plug @ 800 w/80sks 10sks In Mouse Hole plugs displaced with Mud
3rd Plug @ 250 w/40sks 205sks Total 60/40Poz 6%Gel w/1#FS/sk By Allied Cementing
4th Plug @ 40 w/10sks Completed @ 6:30AM 2/13/96

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Discovery Drilling, Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601-0763

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Diamond Oil, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Kenneth Vehige

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed: the same are true and correct, so help me God.


RECEIVED
KANSAS CORPORATION COMMISSION

(Signature) [Signature]

P.O. Box 641

(Address)

AND SWORN TO before me this 1st day of May, 1996



CONSERVATION DIVISION

WICHITA, KS 67-18-99

Notary Public Verda M. Brin

My Commission Expires: _____