

RECEIVED

DEC 19 2002
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Lundy-Hair

WELL NUMBER 1

660 Ft. from N Section LI

410 Ft. from W Section LI

SEC. 4 TWP. 20S RGE. 24W (X) or (W)

COUNTY Ness

Date Well Completed 12/31/60

Plugging Commenced 10/27/02

Plugging Completed 10/29/02

LEASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE (785) 798-3641 OPERATORS LICENSE NO. 31627

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/24/02 (date)

by Mike Maier, District #1 (KCC District Agent's Name)

Is ACO-1 filled? yes If not, is well log attached? _____

Producing Formation Mississippian Depth to Top Open Hole Bottom T.O. 4473

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size 5 1/2 | Put In 4470 | Pulled out 430 |
|-----------|---------|------|----|---------------|----------------|-------------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl... were used, state the character of same and depth placed, from feet to feet each s...
10/27/02 Sanded casing off to 4200' & dumped 2 sks of cement thru a dump bailer. 10/28/02 Swift pumped a 50 sk plug @ the casing leak, displaced & shut in overnight. 10/29/02 Shot casing off @ 720' & tried to pull casing. Could not pull it, pumped an 80 sk plug & displaced it to 700'. Cut off casing @ 430', pulled casing to 300' & spotted a 40 sk plug. Pulled 5 1/2" & filled the 8 5/8" with 10 more sks. Job complete.


Name of Plugging Contractor Swift Services Inc License No. _____

Address P O Box 466, Ness City, KS 67560-0466

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fa... statements, and matters herein contained and the log of the above-described well as filed i... the same are true and correct, so help me God.



(Signature) Mike J. Fritzler

(Address) P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN to before me this 18th day of December 2002, ss.

Debra Kerr
Debra Kerr Notary Public

My Commission Expires: 4/20/05

USE ONLY ONE SIDE OF EACH FORM

CR