

15-135-20169-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ness County. Sec. 25 Twp. 20S Rge. (E) 24 (W)

Location as "NE/CNW/SW" or footage from lines C/NE NW
Lease Owner R. V. Lehner
Lease Name Cranston Well No. 3
Office Address P. O. Box 398, Ness City, Kansas 67560
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 28 19 68
Application for plugging filed July 28 19 68
Application for plugging approved July 28 19 68
Plugging commenced July 28 19 68
Plugging completed July 28 19 68
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4378 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	282.17'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: Plugged at 720' with 70 sacks of cement; plugged at 280' with 20 sacks of cement; plugged at 40' with 10 sacks of cement. Plug down at 5:50 P. M. July 28, 1968.

RECEIVED
STATE CORPORATION COMMISSION
JUL 31 1968
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp
P. O. Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 68



Elaine H. Taylor
Notary Public.

DRILLERS LOG

#3 Cranston

CASING RECORD:
282.17' of new 8-5/8"
surface casing.

COMPANY: R. V. Lehner
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/NE NW
Section 25-20S-24W
Ness County, Kansas

TOTAL DEPTH:
4378'

COMMENCED: July 19, 1968
COMPLETED: July 28, 1968

ELEVATION: 2278' DF

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Post Rock, Sand & Blue Shale	0	250	Ran 282.17' of new 8-5/8" surface casing; set and cemented at 282.17' with 155 sacks of regular cement. Plug down at 2:30 P. M. July 20, 1968.
Shale	250	350	
Shale, Shells, Blue Shale and Red Bed	350	1005	
Sand & Shale	1005	1475	
Shale, Shells w/Lime Streaks	1475	1810	
Shale & Lime	1810	3920	
Lime	3920	4335	
Lime & Chert	4335	4378	

Total Depth 4378'

D. & A.

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1 1968
CONSERVATION DIVISION
Wichita, Kansas

Plugged hole as follows: Plugged at 720' with 70 sacks of cement; plugged at 280' with 20 sacks of cement; plugged at 40' with 10 sacks of cement. Plug down at 5:50 P. M. July 28, 1968.

STATE OF KANSAS)
)ss.
COUNTY OF BARTON))

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 29th day of July, 1968.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

