

K-135-20542-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 17 Twp. 20S Rge. (E) 24 (W)
Location as "NE/CNW/SW" or footage from lines C/SW NW
Lease Owner Strata Drilling, Inc.
Lease Name Copeland Well No. 1
Office Address P. O. Box 355, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 28 19 71
Application for plugging filed December 28 19 71
Application for plugging approved December 28 19 71
Plugging commenced December 28 19 71
Plugging completed December 28 19 71
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4442 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	296'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Plugged hole as follows: Plugged at 600' with 70 sacks of 50-50 pozmix; plugged at 290' with 20 sacks of pozmix; plugged at 40' with 10 sacks of pozmix. Plug down at 5:10 P. M. December 28, 1971.

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner/lessee) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of December, 19 71

My Commission expires December 14, 1973
Elaine H. Taylor
Notary Public.



K-135-20542-0000

D R I L L E R S L O G

#1 Copeland

CASING RECORD: Pipe set by Cimarron Drillers, Inc.	COMPANY: Strata Drilling, Inc.	DESCRIPTION: C/SW NW Section 17-20S-24W Ness County, Kansas
TOTAL DEPTH: 4442'	CONTRACTOR: Strata Drilling, Inc.	ELEVATION: 2342' RB
	COMMENCED: December 18, 1971	
	COMPLETED: December 28, 1971	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Post Rock & Sand	0	305	Surface set by Cimarron Drillers, Inc.
Shale	305	992	
Shale & Red Bed	992	1049	
Dakota Sand	1049	1307	
Red Bed & Shale	1307	1589	
#2 Anhydrite	1589	1601	
Shale, Shells & Rock Lime	1601	2125	
Shale, Lime w/Broken Lime	2125	2360	
Lime	2360	2536	
Lime & Shale	2536	4002	
Lime	4002	4234	
Lime & Shale	4234	4307	
Lime	4307	4310	
Lime & Shale	4310	4370	
Lime	4370	4388	
Cherty Lime & Shale	4388	4427	
Chert, Lime & Shale	4427	4442	

Rotary Total Depth 4442'

D. & A.

Plugged hole as follows: Plugged at 600' with 70 sacks of 50-50 pozmix; plugged at 290' with 20 sacks of 50-50 pozmix; plugged at 40' with 10 sacks of 50-50 pozmix. Plug down at 5:10 P. M. December 28, 1971.

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1972
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 30th day of December, 1971.

My Commission Expires:
December 24, 1973

Elaine H. Taylor
Elaine H. Taylor, Notary Public

