

15-135-20077-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ness County, Sec. 25 Twp. 20S Rge. (E) 24 (W)  
Location as "NE/CNW&SW" or footage from lines C/SE NE  
Lease Owner R. V. Lehner  
Lease Name Cranston Well No. 2  
Office Address P. O. Box 398, Ness City, Kansas 67560  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 8 1967  
Application for plugging filed November 8 1967  
Application for plugging approved November 8 1967  
Plugging commenced November 8 1967  
Plugging completed November 8 1967  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4413 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	289'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole as follows: Plugged at 720' with 100 sacks of cement; plugged at 300' with 25 sacks of cement; plugged at 40' with 10 sacks of cement. Plug down at 8:30 A. M. November 8, 1967.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 12 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.  
Address P. O. Box 355, Great Bend, Kansas 67530


STATE OF KANSAS, COUNTY OF BARTON, ss.  
Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
Charles W. Steincamp  
P. O. Box 355, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 1967

My commission expires December 14, 1969

Elaine H. Taylor Notary Public.



15-135-20077-0000

DRILLERS LOG

#2 Cranston

CASING RECORD:  
289' of used 8-5/8"  
surface casing.

COMPANY: R. V. Lehner  
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/SE NE  
Section 25-20S-24W  
Ness County, Kansas

TOTAL DEPTH:  
4413'

COMMENCED: October 27, 1967  
COMPLETED: November 8, 1967

ELEVATION: 2270' KB

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Rock & Shale	0	293	Ran 289' of used 8-5/8" surface casing; set and cemented at 289' with 160 sacks of common sunset cement and 2% gel. Plug down at 10:30 A. M. October 28, 1967.
Shells & Shale	293	873	
Anhydrite	873	890	
Shale & Shells	890	1502	
Anhydrite	1502	1516	
Shale	1516	1545	
Shale w/Lime Streaks	1545	1875	
Shale & Lime	1875	4100	
Lime	4100	4413	

Total Depth 4413'

RECEIVED  
NOV 13 1967  
CONSERVATION DIVISION  
Wichita, Kansas

D. & A.

Plugged hole as follows: Plugged at 720' with 100 sacks of cement; plugged at 300' with 25 sacks of cement; plugged at 40' with 10 sacks of cement. Plug down at 8:30 A. M. November 8, 1967.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
Charles W. Steincamp, President

Subscribed and sworn to before me this 9th day of November, 1967.

My Commission Expires:  
December 14, 1969

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public