

K-135-20612-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 20 Twp. 20S Rge. (E) 24 (W)

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Okmar Oil Company
Lease Name Pember Well No. 1
Office Address 1130 Wichita Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 10 1972
Application for plugging filed June 10 1972
Application for plugging approved June 10 1972
Plugging commenced June 10 1972
Plugging completed June 11 1972
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4453 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	303.78			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged as follows: Plugged at 650' with 70 sacks of common cement; plugged at 280' with 20 sacks of common cement; plugged at 40' with 10 sacks of common cement. Plug down at 2:00 A. M. June 11, 1972.

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of June, 1972

My commission expires December 14, 1973



Elaine H. Taylor
Elaine H. Taylor Notary Public.

15-135-28612-0000

DRILLERS LOG

#1 Pember

CASING RECORD:
297.78' of used 8-5/8"
surface casing.

COMPANY: Okmar Oil Company
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/SW SE
Section 20-20S-24W
Ness County, Kansas

TOTAL DEPTH:
4453'

COMMENCED: May 30, 1972
COMPLETED: June 11, 1972

ELEVATION: 2346' K.B.

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Post Rock, Sand & Shale	0	87	Ran 297.78' of used 8-5/8" surface casing; set and cemented at 303.78' with 175 sacks of common cement, 2% gel and 3% C. C. Plug down at 5:40 A. M. May 31, 1972.
Clay	87	333	
Clay & Shale	333	489	
Shale, Red Bed	489	944	
#1 Anhydrite	944	950	
Red Bed	950	1063	
Dakota Sand	1063	1320	
Shale	1320	2153	
Broken Lime & Shale	2153	2298	
Lime & Shale	2298	2508	
Lime	2508	2646	
Broken Lime & Shale	2646	2802	
Lime & Shale	2802	2902	
Lime	2902	3138	
Shale & Lime	3138	3346	
Lime, Shale w/Sand Streaks	3346	3566	
Lime & Shale	3566	4120	
Lime	4120	4211	
Lime & Shale	4211	4246	
Lime	4246	4345	
Lime, Shale & Chert	4345	4360	
Lime	4360	4437	
Chert & Shale	4437	4445	
Lime, Chert & Sand	4445	4453	

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1972
CONSERVATION DIVISION
Wichita, Kansas

D. & A.

Ran Great Guns R. A. Guard Log.

ROTARY TOTAL DEPTH: 4453'

Plugged as follows: Plugged at 650' with 70 sacks of common cement; plugged at 280' with 20 sacks of common cement; plugged at 40' with 10 sacks of common cement. Plug down at 2:00 A. M. June 11, 1972.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 13th day of June, 1972.

My Commission Expires:

December 14, 1973

Elaine H. Taylor
Elaine H. Taylor, Notary Public

