


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Hodgeman County, Sec. 4 Twp. 24S Rge. 21W (E) (W)  
Location as "NE/CNVKSW" or footage from lines Apx. SW SW  
Lease Owner Hershberger Explorations, Inc.  
Lease Name Burke Well No. 1  
Office Address Suite 230, Garvey East, 200 W. Douglas, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D&A  
Date well completed Feb. 5, 1973  
Application for plugging filed Feb. 5, 1973  
Application for plugging approved Feb. 5, 1973  
Plugging commenced Feb. 5, 1973  
Plugging completed Feb. 5, 1973  
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eyes  
Producing formation Depth to top Bottom Total Depth of Well 4679 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
				8 5/8"	263'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug @ 800' w/35 sx cement, plug @ 260' w/35 sx,  
Plug-bridge to hold Kelly  
@ 40' w/15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Red Tiger Drilling Company  
Address 1720 Wichita Plaza, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Gloria Fawcett (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett  
1720 Wichita Plaza, Wichita, Kansas (Address)

Subscribed and sworn to before me this 7th day of February, 1973



My commission expires 22-74 Notary Public.

DRILLERS LOG

No. 1 Burke

CASING RECORD:	COMPANY:	Hershberger Explorations, Inc.	DESCRIPTION:
8 5/8" @ 263' w/175 sx cement	CONTRACTOR:	Red Tiger Drilling Company	Box. SW SW 4-24S-21W Hodgeman County, Kansas
	COMMENCED:	January 24, 1973	
	COMPLETED:	February 5, 1973	
TOTAL DEPTH: 4679'			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & shale	0	265	
Rat hole	265	396	
Shale & red bed	396	920	
Sand	920	1125	
Shale & shells	1125	1444	
Anhydrite	1444	1462	
Shale	1462	1500	
Red bed	1500	1574	
Anhydrite	1574	1602	
Shale & shells	1602	1765	
Shale & lime	1765	3770	
Shale, Chalky lime	3770	4035	
Lime	4035	4679	

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1973  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett  
Gloria Fawcett

Subscribed and sworn to before me this 7<sup>th</sup> day of February, 1973.

Sean Hollan  
Notary Public

