

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-20,418 -0000

LEASE NAME Betz 'A'

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3300' Ft. from S Section Line
1980' Ft. from E Section Line

SEC. 13 TWP. 20 RGE. 23 (E) or (W)

COUNTY Ness

Date Well Completed 3/10/71

Plugging Commenced 3/18/92

Plugging Completed 3/18/92

LEASE OPERATOR DaMar Resources, Inc.

ADDRESS P. O. Box 70 Hays, KS 67601

PHONE#(913) 625-0020 OPERATORS LICENSE NO. 9067

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/18/92 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? ? If not, is well log attached? yes

Producing Formation Fort Scott Depth to Top 4224 Bottom 4247 T.D. 4341

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Fort Scott	Oil	4247'	4341	8 5/8"	329'	none
				5 1/2"	4337'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump 15 sx 60/40 pozmix cement w/6% gel down 8 5/8"-5 1/2" annulus, pressured up to 500#.
Pump 285 sx 60/40 pozmix cement w/6% gel and 800 lbs. cotton seed hulls down 5 1/2" casing at 0# pressure, hole stood full of cement at end of pumping.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing

Address 24 S. Lincoln Russell, KS 67605

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DaMar Resources, Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Curtis R. Longpine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Curtis R. Longpine

(Address) P. O. Box 70 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 24th day of March, 19 92



Vickie Cole
Notary Public
7-10-95