

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market - Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-20,192-0000

LEASE NAME Maranville 'B'

WELL NUMBER #1

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 13 TWP. 20 RGE. 23 (E) or (W)

COUNTY Ness

Date Well Completed 11/68

Plugging Commenced 7/27/00

Plugging Completed 7/27/00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR DaMar Resources, Inc.

ADDRESS P. O. Box 70 Hays, KS 67601

PHONE# (785) 625-0020 OPERATORS LICENSE NO. 9067

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/24/00 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? ? If not, is well log attached? no; attached to CP-1

Producing Formation Ft. Scott/Miss. Depth to Top 4222 Bottom 4343 T.D. 4343

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	282	none
				5 1/2	4333	none

RECEIVED  
STATE CORPORATION COMMISSION  
AUG - 7 2000  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Spot 35 sx cement w/200# hulls @ 4295; spot 130 sx cement w/400# hulls @ 450; pump 75 sx down casing; pump 10 sx down 8 5/8 - 5 1/2 annulus - pressure to 500#. Used 60/40 pozmix cement w/6% gel. After 4 days cement fell 450'; filled casing with 60 sx cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. NA

Address P. O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DaMar Resources, Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Curtis R. Longpine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 70 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 4th day of August, 2000, 19



[Signature]  
Notary Public