

LEASE NAME Whitley

WELL NUMBER 2" Twin"

3150 Ft. from S Section Line

810 Ft. from E Section Line

SEC. 13 TWP. 20 SRGE. 23 W (S) or (W)

COUNTY Ness

Date Well Completed 9-2-80

10:30 A.M.

Plugging Commenced 12-29-98

3:45 P.M.

Plugging Completed 12-29-98

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Buried Hills Production Co., Inc.

ADDRESS 1050 17th Street Suite 1550 Denver, Co.

PHONE (303) 595-0125 OPERATORS LICENSE NO. 31961

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-28-98 (date)

by Steve Durrant (KCC-District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Miss. Depth to Top 4321' Bottom 4328' T.D. 4328'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Casing	Surface	0	253'	85/8"	253'	None
	Prod. string	0	4321'	4 1/2"	4321'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Run 2" tubing And Packer to 775". Pressure to 500#. Did not leak off.  
Pull packer and tubing out. Run tubing to 4300'. Mix 35sks. of 60/40 Posmix 6% gel with 100# of hulls. Pull tubing to 1500'. Mix 30sks. of cement with 100# of  
Pull tubing. Perf @ 750'. Pump down casing 145sks. with 300# hulls. Pump down ann. 25sks. pressure to 500# close well in.

Name of Plugging Contractor Allied Cementing Company License No. \_\_\_\_\_

Address RHssEll, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Buried Hills Prod. Co., Inc. 11 1994

STATE OF Kansas COUNTY OF Ellis

Dean Ives (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Dean Ives

(Address) 1209 Hancey Hays, Ko.

7th day of January, 19 99

Charlotte Weber

Notary Public



My Commission Expires: 12-28-99