

15.135-30231-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ness County, Sec. 13 Twp. 20S Rge. 23W (E) (W)

Location as "NE/CNW&SW&" or footage from lines C SWSW
Lease Owner Shell Oil Company
Lease Name Maranville Well No. 2-13
Office Address 1200 First National Bldg., Okla. City, Okla. 73102
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-14-66 19
Application for plugging filed 7-14-66 19
Application for plugging approved 7-14-66 19
Plugging commenced 7-14-66 19
Plugging completed 7-14-66 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4370 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded to 540', set plug w/25 sks. cem. through drill pipe
Mudded to 250', set plug w/20 sks. cem. through drill pipe
Mudded to 40', set plug w/10 sks. cem.

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of July, 19 66



My commission expires April 1, 1967

Alanda Nichols
Notary Public.

DRILLER'S LOG

COMPANY: Shell Oil Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: MARANVILLE #2-13
 LOCATION: C SW SW SEC. 13-20S-23W
 NESS COUNTY, KANSAS
 COMMENCED: 7-3-66
 COMPLETED: 7-14-66

0	250	Surface Clay, Sand
250	715	Shale
715	910	Shale, Redbed
910	1100	Sand
1100	1441	Shale
1441	1492	Anhydrite
1492	1497	Shale
1497	2000	Shale, Shells
2000	2346	Shale, Lime
2346	2840	Lime
2840	3150	Lime, Shale
3150	3455	Shale, Lime
3455	3572	Lime, Shale
3572	3720	Lime, Chalky Shale
3720	4370	Lime
	<u>4370</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 19 1966
 CONSERVATION DIVISION
 WICHITA, KANSAS

Set 8 5/8" 20# new surface casing @ 250' with landing joint cemented with 185 sacks Common cement, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Maranville #2-13 well, located C SW SW for Section 13, Township 20 South, Range 23 West, Ness County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 16th day of July, 1966.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
 April 1, 1967

