


15.135.20214-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Ness County. Sec. 7 Twp. 20S Rge. 24 W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C NW NE  
Lease Owner Pickrell Drilling Company  
Lease Name Betz "E" Well No. 2  
Office Address 705 4th National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 1, 1968 19  
Application for plugging filed December 1, 1968 19  
Application for plugging approved December 1, 1968 19  
Plugging commenced December 1, 1968 19  
Plugging completed December 1, 1968 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4460 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	267'	


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 660'. Set plug. Cemented with  
70 sacks cement. Heavy mud to 240'. Set plug.  
Cemented with 20 sacks of cement. Heavy mud to  
40'. Set plug. Cemented with 10 sacks of cement  
to bottom of cellar. Plugged rat hole with 2  
sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 4th National Bank Bldg, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
(employee of owner) or (owner or operator) of the above-described  
well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above described well as filed and that the same are true and correct. So help me God.



(Signature) C. W. Sebirs  
705 4th National Bank Bldg, Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 4th day of December, 19 68

L. M. Whiting  
L. M. Whiting Notary Public.

15-35-20214-0000  
**ROTARY DRILLING LOG**

**COMPANY:** PICKRELL DRILLING COMPANY  
 705 4th National Bank Bldg.  
 Wichita, Kansas

**LOCATION:** ~~Bozwell~~ No. 2, C NW NE Sec. 07-20S-24W  
 Ness County, Kansas

Rotary Drilling Commenced 11-20-68  
 Rotary Drilling Completed 12-1-68

**CONTRACTOR:** **PICKRELL DRILLING COMPANY**  
 Wichita, Kansas

**CASING RECORD:** Ran 17 jts. used 28# 8 5/8" casing set 267'KB, cemented with 160 sacks. Circulated. Completed 7:00 PM, November 20, 1968. No oil, string run. D & A.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Clay & Post Rock	
268	Shale & Shells	<u>C. F. S.</u>
750	Shale	4302
960	Shale & Red Bed	4315
981	Blaine	4332
1065	Shale, Sand Stringers	4388
1272	Sand	4400
1579	Shale	4405
1579	Anhydrite	4415
2200	Shale	4420
2537	Shale & Lime	4425
2760	Lime & Shale	4431
2840	Shale & Lime	4435
2990	Shale	4460
3110	Shale & Lime	
3470	Shale	<u>Slope Test</u>
3610	Shale & Lime	2000
3735	Shale	2500
3880	Shale & Lime	3000
3933	Lime & Shale	3500
3987	Lime	4000
4150	Lime & Shale	
4265	Lime	
4370	Lime & Shale	<u>S. L. M.</u>
4460	Mississippian RTD	

Board 4244.03  
 Strap 4242.83  
 Difference + 1.80

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 DEC 10 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

**PICKRELL DRILLING COMPANY**  
 By [Signature]  
 C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
 COUNTY OF NEBICK } ss.:

On this \_\_\_\_\_ day of December \_\_\_\_\_, 1968, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]  
 L. M. Whiting Notary Public

