


15.135-30170-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 11 Twp. 20 Rge. 24 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. NE SW SW
Lease Owner Leben Drilling, Inc.
Lease Name Petersilly "C" Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6-15-66 _____ 19____
Plugging completed 6-18-66 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well L. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4471 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	260'	None
				5-1/2"	4440'	3344'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4471', sanded to 4425' and dumped 5 sacks of cement @ 4425' with dump bailer. Pulled 5 1/2" casing to 560' and circulated with 25 sacks of gel mud. Pulled 5 1/2" casing to 500' and pumped in 30 sacks of cement. Pulled 5 1/2" casing to 240' and pumped in 25 sacks of cement. ~~XXX~~ Pulled balance of 5 1/2" casing, bailed fluid to 30' and dumped 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 5 1966

CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or ~~former operator~~

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of June, 1966

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

DRILLER'S LOG

COMPANY: Leben Drilling, Inc.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: PETERSILIE C-#1
 LOCATION: NE SW SW Sec. 11-20S-24W
 NESS COUNTY, KANSAS
 COMMENCED: 3-23-66
 COMPLETED: 4-2-66

0	262	Clay, Shale
262	949	Shale
949	961	Blaine
961	1035	Redbed
1035	1250	Sand
1250	1572	Shale, Shells
1572	1605	Anhydrite
1605	2200	Shale, Shells
2200	2410	Shale, Lime
2410	3040	Lime, Shale
3040	3375	Lime, Chalky Shale
3375	3699	Lime, Chalk
3699	4370	Lime
4370	4428	Lime, Chert
4428	4445	Lime
	4445	RTD - Set 5 1/2" Casing

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 19 1966
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" used surface casing @ 260' with landing joint cemented with 150 sacks Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Petersilie C-#1 well, located NE SW SW of Section 11, Township 20 South, Range 24 West, Ness County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 7th day of April, 1966.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1967