

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67702

WELL PLUGGING RECORD
K.A.R.-82-3-117

071

API NUMBER 15-083-20293 00 01

Lease Name Rosenberg A

WELL NUMBER 1

2970 Ft. from S Section Line

4940 Ft. from E Section Line

SEC. 12 TWP. 16S RGE. 43W (E) or (W)

COUNTY Greeley

Date well completed 5/21/83

Plugging Commenced 6/8/99

Plugging completed 6/9/99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Herman L. Loeb

Address P O Box 524 Lawrenceville, IL 62439

Phone (618) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well Input

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 1999 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, IS well log attached? _____

Producing Formation Morrow Depth to Top 5130 Bottom 5156 T.D. 5285

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Oil</u>	<u>5130</u>	<u>5156</u>	<u>8 5/8"</u>	<u>503</u>	<u>0</u>
				<u>4 1/2"</u>	<u>5285</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, State the character of same and depth placed, from feet to feet each set
Set cast iron bridge plug @ 4787', spot 2 sk of cement on top of plug. Run tubing & packer to 1941', pressure test annulus above packer to 300 psi, holds ok. POH w/ tubing & packer. Set CIBP @ 1935', RIH w/ tubing to 1915', circulate cement to surface. POH w/ tubing. Top off casing. Use 135 sk 60/40 pozmix w/ 6% gel. Pressure test surface casing to 500 psi, holds ok.

Name of Plugging Contractor Key Rocky Mountain License No. 05866

Address P O Box 69 Cheyenne Wells, CO 80810

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb

STATE OF Illinois COUNTY OF Lawrence '33.


George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God. (Signature) George A. Payne

(Address) 7588 Marywood Drive Newburgh IN 47630

Subscribed and sworn to before me this 28 day of July, 19 99

Donna Carlene Lucas
Notary Public

My commission expires: 4-6-02



RECEIVED
STATE CORPORATION COMMISSION

AUG - 2 1999
8-2-99
CONSERVATION DIVISION
Wichita, Kansas