

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-071-20,308-002 <sup>01</sup>

LEASE NAME White "AB"

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 12 TWP. 16S RGE. 43 ~~(E)~~ or (W)

LEASE OPERATOR TXO Production Corp.

ADDRESS 1800 Lincoln Center Bldg., Denver, Colorado 80264

COUNTY Greeley

PHONE#(303) 861-4246 OPERATORS LICENSE NO. 5171

Date Well Completed 10/18/83

Character of Well P & A

Plugging Commenced 1/3/85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1/4/85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is AC0-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Water	0	457	8-5/8"	457'	0
		1950	5300	4 1/2"	5300'	1951'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

A 4 1/2" CIBP was set @ 5100' & 2 sxs of cmt dump bailed, a 25 sx plug was set @ the 4 1/2" csg stub from 1850'-2050', a 25 sxs plug was set @ the base of the 8-5/8" surface pipe from 400'-480'. A 10 sx plug was set from 40' to surface. The csg was cut 3' below the surface and a cap welded on. All plugs were spotted.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License STATE CORPORATION COMMISSION

Address Lamar

STATE OF Colorado COUNTY OF Prowers, ss.

RECEIVED

1-28-85  
JAN 28 1985

CONSERVATION DIVISION

Frank D. Tsuru (Employee of Operator) or Wichita, Kansas of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Frank D. Tsuru

(Address) 1800 Lincoln Center Bldg. Denver, Colorado 80264

SUBSCRIBED AND SWORN TO before me this 24 day of January, 19 85

Nada J. Branson  
Notary Public

My Commission Expires: Dec. 04, 1985  
9220 Perry St., Westminster, CO 80031

