

API NUMBER 15-071-20336-0001

Lease Name Otis

WELL NUMBER # 7

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

4290 Ft. from S Section Line

1550 Ft. from E Section Line

SEC. 12 TWP. 16S RGE. 43W ( E ) or ( W )

COUNTY Greeley

Date well completed 10/7/84

Plugging Commenced 9/27/99

Plugging completed 9/27/99

LEASE OPERATOR Herman L. Loeb

Address P. O. Box 524 Lawrenceville, IL 62439

Phone ( 618 ) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well Input

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/25/99 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, IS well log attached? no

Producing Formation Morrow Depth to Top 5140' Bottom 5173' T.D. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>oil</u>	<u>5140'</u>	<u>5173'</u>	<u>8 5/8"</u>	<u>464'</u>	<u>0'</u>
				<u>4 1/2"</u>	<u>5300'</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Set cast iron bridge plug @ 5100', spot 2 sk of cement on top w/ dump bailer. Set cast iron bridge plug @ 2000'. RIH w/ tubing to 1980'. Pump 105 sk of cement, pull tubing to 600 ft, pump 10 sk cement, circulate to surface (0' to 1980'). POH w/ tubing. Pump 7 sk cement down 4 1/2" x 8 5/8" annulus. Used 60/40 pozmix w/ 6% gel.

Name of Plugging Contractor Mull Drilling License No. 5144

Address P O Box 2758 Wichita, KS 67201-2758

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb


STATE OF Illinois COUNTY OF Lawrence '33.

George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God. (Signature) George A. Payne

(Address) 7588 Marywood Drive Newburgh, IN 47630

Subscribed and sworn to before me this 12th day of October 19 99

Donna Carlene Lucas  
 Notary Public



Form CP-4

My STATE CORPORATION COMMISSION expires: April 6, 2002

RECEIVED  
 OCT 12 1999  
 10-12-99  
 CONSERVATION DIVISION  
 Wichita, Kansas

(Handwritten initials)