

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67702

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-071-20322 -00-00

Lease Name Otis

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 4

4080 Ft. from S Section Line

650 Ft. from E Section Line

SEC. 12 TWP. 16S RGE. 43W (E) or (W)

COUNTY Greeley

Date well completed 8/28/84

Plugging Commenced 12/3/2001

Plugging completed 12/4/2001

LEASE OPERATOR Herman L. Loeb

Address P. O. Box 524 Lawrenceville, IL 62439

Phone ( 618 ) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/30/02 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, IS well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 5146' Bottom 5177' T.D. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Run 2" tubing to 3,400', pump 40 sk cement w/ 200# of hulls. POH w/ tubing. Set cast iron bridge plug @ 1,650', perforate 3 holes @ 1,600'.

Pump 170 sk cement down 4 1/2" casing. Hook on to annulus between 4 1/2" and 8 5/8", pump 200 sk down annulus. All cement 60/40 pozmix w/ 6% gel. Used 400# of hulls total.

Name of Plugging Contractor Eastern Colorado Well Service License No. 32524

Address P O Box 244 Cheyenne Wells, CO 80810

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb

STATE OF Illinois COUNTY OF Lawrence '33.

George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God.

(Signature) George A. Payne

(Address) P O Box 743, Newburgh, IN 47629-0743

Subscribed and sworn to before me this 2nd day of January, 19 2002

Judith A. Moore  
Notary Public

My commission expires: 9-20-07

KANSAS CORPORATION COMMISSION

Form CP-4

JAN 07 2002  
1-7-02

CONSERVATION DIVISION

OR