

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-071-20,306-0000

LEASE NAME Rosenberg

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER "A" #3

4000 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 12 TWP. 16S RGE. 43 (E) or (W)

COUNTY Greeley

Date Well Completed 10/2/83

Plugging Commenced 1/18/85

Plugging Completed 1/19/85

LEASE OPERATOR TXO Production Corp.

ADDRESS 1800 Lincoln Center Bldg., Denver, COLO 80264

PHONE#(303) 861-4246 OPERATORS LICENSE NO. 5171

Character of Well P & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 5171 Bottom 5173 T.D. 5291

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Water	0	457	8-5/8"	457	None
		1209'	5300'	4 1/2"	5300	1209'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

A 4 1/2" CIBP was set @ 5100' & capped w/ 2 sxs of cmt, a 25 sx plug was set @ the 4 1/2" csg stub from 1100 to 1300'. A 25 sx plug was set @ the base of the 8-5/8" surface pipe from 400-490', a 10 sx plug was set from 40' to surface. The csg was cut 3' below the surface and a cap was welded on. All plugs were set through csg.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. \_\_\_\_\_

Address Lamar


STATE OF Colorado COUNTY OF Prowers, ss.

RECEIVED  
 STATE CORPORATION COMMISSION  
 1-28-85  
 JAN 28 1985

Frank D. Tsuru (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Frank D. Tsuru

(Address) 1800 Lincoln Center Bldg. Denver, Colorado 80264



SUBSCRIBED AND SWORN TO before me this 24 day of January, 19 85

Nada J. Branson  
 Notary Public

My Commission Expires: Dec. 14, 1986  
9220 Perry St., Westminster, CO 80031