

API NUMBER 15-071-20316 - 0000
 Lease Name Rosenberg A

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 4
4290 Ft. from S Section Line
4900 Ft. from E Section Line
 SEC. 12 TWP. 16S RGE. 43W (E) or (W)
 COUNTY Greeley
 Date well completed 4/3/84
 Plugging Commenced 9/8/99
 Plugging completed 9/8/99

LEASE OPERATOR Herman L. Loeb
 Address P. O. Box 524 Lawrenceville, IL 62439

Phone (618) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well Oil
 Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/2/99 (date)
 by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, IS well log attached? no

Producing Formation Morrow Depth to Top 5132' Bottom 5148' T.D. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>oil</u>	<u>5132'</u>	<u>5148'</u>	<u>8 5/8"</u>	<u>454'</u>	<u>0'</u>
				<u>4 1/2"</u>	<u>5292'</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Cast iron bridge plug previously set @ 5100' w/ 2 sk of cement on top. Attempt to run tubing & packer below perforations at 1010-22'.

Tubing tags something at 1,250 ft (probable bridge plug). POH w/ tubing & packer. RU Allied Cementing, hook on to 4 1/2" casing. Establish injection rate, pump 140 sk cement w/ 200# of hulls (0' to 1010'). Hook on to surface casing, pump 70 sk cement down 4 1/2" x 8 5/8" annulus.

Name of Plugging Contractor None, no rig on the well. License No. _____

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb


STATE OF Illinois COUNTY OF Lawrence '33.

George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God. (Signature) George A. Payne

(Address) 7588 Marywood Drive Newburgh, IN 47630

Subscribed and sworn to before me this 12th day of October, 19 99

Donna Carlene Lucas
 Notary Public



Form CP-4

My State Commission Expires: April 6, 2002

RECEIVED
 OCT 12 1999
 10-12-99
 CONSERVATION DIVISION
 Wichita, Kansas

R