

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-071-20328-0000

LEASE NAME Rosenberg

WELL NUMBER A #5

3630 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 12 TWP. 16 SRGE. 43 (E) or (W)

LEASE OPERATOR TXO Production Corp.

ADDRESS 1800 Lincoln Center Bldg., Denver, Colorado 80264 COUNTY Greeley

PHONE# (303) 861-4246 OPERATORS LICENSE NO. 5171 Date Well Completed 9/30/84

Character of Well P & A Plugging Commenced 1/16/85

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 1/17/85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 5131 Bottom 5154 T.D. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|-------|------|--------|--------|------------|
| Morrow | Water | 0 | 492 | 8-5/8" | 492' | None |
| | | 1100' | 5300 | 4 1/2" | 5300' | 1100' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

A 4 1/2" CIBP was set @ 5100' w/ a 2 sx cmt plug set on top. A 25 sx plug was set from 1200'-1000'. A 25 sx plug was set @ the base of the 8-5/8" csg from 500-420', a 10 sx plug was set @ 40' to surface. The casing was cut off 3' below surface & a cap was welded on.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 1-28-85

Address Lamar

STATE OF Colorado COUNTY OF Prowers, ss.

RECEIVED
 STATE CORPORATION COMMISSION
 1-28-85
 JAN 28 1985
 CONSERVATION DIVISION
 Wichita, Kansas

Frank D. Tsuru (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Frank D. Tsuru
 1800 Lincoln Center Bldg.

(Address) Denver, Colorado 80264

SUBSCRIBED AND SWORN TO before me this 24 day of January, 19 85

Nada J. Branson
 Notary Public

My Commission Expires: My Commission Expires Dec. 15, 1985
 320 Perry St., Westminster, CO 80030

