

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME MAH TWIN
 WELL NUMBER 2
660 Ft. from S Section Line
4620 Ft. from E Section Line
 SEC. 22 TWP. 17S RGE. 39 (E) or (W)
 COUNTY CREEKEY
 Date Well Completed 2/4/78
 Plugging Commenced 5/2/96
 Plugging Completed 5/2/96

LEASE OPERATOR GARY ADAMS OIL + GAS
 ADDRESS P.O. BOX 21470 Tulsa, Okla 74121
 PHONE# (918) 582-7713 OPERATORS LICENSE NO. 6161
 Character of Well SWD
 (Oil, Gas, D&A, SWD Input, Water Supply Well)

The plugging proposal was approved on MARCH 26, 1996 (date)
 by DAVID WILLIAMS (KCC District Agent's Name)

Is ACO-1 filed? YES If not, Is well log attached? _____
 Producing Formation CHASE / FT RIKY Depth to Top 2906 Bottom 3011 T.D. 3075
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>SURFACE</u>		<u>0</u>	<u>2100</u>	<u>8 5/8</u>	<u>260</u>	<u>NONE</u>
<u>CHASE</u>	<u>SANDSTONE</u>	<u>0</u>	<u>3068</u>	<u>5 1/2</u>	<u>3068</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pulled Packse and Tubing. Pumped 5 SK Cement down Backside. Pressured to 300 PSI. Pumped 270 SK 60/40 Poz w/ 4 SK HULLS VIA 5 1/2 Casing. Filled to SURFACE. Pressured to 700 PSI. NO FAIR BACK CUT 5 1/2 AND 8 5/8 DIA 4' BELOW SURFACE + Capped.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor GARY ADAMS OIL + GAS License No. 6161
 Address P.O. BOX 21470 Tulsa, Okla 74121
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GARY ADAMS OIL + GAS
 STATE OF _____ COUNTY OF _____, ss.

WADE J. ALEXANDER (Employee of Operator) (Operator) of above-described well, being first duly sworn on oath, says that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well has filed that the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) _____

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 96
[Signature]
 Notary Public

My Commission Expires: 2-21-2000

RECEIVED
 MANSAS OCS
 1996 AUG - 7 11 AM