

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67702

WELL PLUGGING RECORD  
K.A.R. -82-3-117

API NUMBER 15-071-20309-0006

Lease Name Cheek A

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2970 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 11 TWP. 16S RGE. 43W ( E ) or ( W )

COUNTY Greeley

Date well completed 12/83

Plugging Commenced 8/25/99

Plugging completed 8/26/99

LEASE OPERATOR Herman L. Loeb

Address P. O. Box 524 Lawrenceville, IL 62439

Phone ( 618 ) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well \_\_\_\_\_

Oil Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/24/99 (date)

by Steve Durrant (KCC-District Agent's Name)

Is ACO-1 filed? Yes If not, IS well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 5128' Bottom 5142' T.D. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Oil</u>	<u>5128</u>	<u>5142</u>	<u>8 5/8"</u>	<u>461'</u>	<u>0'</u>
				<u>4 1/2"</u>	<u>5300'</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, State the character of same and depth placed, from feet to feet each set  
Set cast iron bridge plug @ 5050', spot 2 sk cement on top. Set cast iron bridge plug @ 1995'. Run tubing to 1995' & pump 170 sk cement.

Cement circulates back to surface. Pull tubing. Hook up to 4 1/2" casing & pump & additional 30 sk. Hook up to 8 5/8" casing & pump 100 sk.

All cement used was 60/40 pozmix w/ 6% gel.

Name of Plugging Contractor Mull Drilling License No. 5144

Address P O Box 2758 Wichita, KS 67201-2758

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb

STATE OF Illinois COUNTY OF Lawrence '33.

George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God. (Signature) George A. Payne

(Address) 7588 Marywood Drive Newburgh, IN 47630

Subscribed and sworn to before me this 22nd day of August, 19 99

Donna Carlene Lucas  
Notary Public

My commission expires: April 6, 2002

