

1060138

TO: STATE CORPORATION COMMISSION

12-29

API NUMBER 15-135-21,855-0000  
150' NE C NW SE SEC. 13, T 20 S, R 23 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME WHITLEY WELL # 2 "TWIN"

TECHNICIAN'S PLUGGING REPORT COUNTY NESS

OPERATOR LICENSE # 31961 WELL TOTAL DEPTH 4328 140.66 FEET

OPERATOR: BURIED HILLS PRODUCTION PRODUCTION CSG: SIZE 4 1/2" @ 4321' WITH 100 SX

NAME AND 1050 17TH ST, STE 1550 SURFACE CASING: SIZE 8 5/8" @ 253' WITH 165 SX

ADDRESS DENVER, CO 80265

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PLAINS INC LICENSE NUMBER 4072

ADDRESS PO BOX 346, NESS CITY, KS 67560-0346

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 29 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM DEAN IVES

(COMPANY NAME) PLAINS INC (PHONE) 785-798-3995

RECEIVED  
STATE CORPORATION COMMISSION

JAN 13 1999  
01-13-99

WERE: PERFS AT 4321-4328

CONSERVATION DIVISION  
Wichita, Kansas

RAN PACKER TO 775' PRESSURED BACKSIDE TO 500# HELD. RAN TUBING JARS FOUND TD AT 4320'.

1ST PLUG AT 4300' WITH 35 SX CEMENT & 100# HULLS. 2ND PLUG AT 1500' WITH 30 SX CEMENT

& 100# HULLS. 3RD PLUG PERFORATED AT 750' AND PUMPED 120 SX NO BLOW- TIED ONTO BACKSIDE

MIXED 25 SX PRESSURED TO 500# AND HELD. PUMPED ANOTHER 25 SX DOWN CASING. SHUT IN WITH

100#. PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:30 PM DAY: 29 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT

RAN PACKER TO 775' PRESSURED BACKSIDE TO 500# HELD. RAN TUBING JARS FOUND TD AT 4320'.

1ST PLUG AT 4300' WITH 35 SX CEMENT AND 100# HULLS. 2ND PLUG AT 1500' WITH 30 SX CEMENT

& 100# HULLS. 3RD PLUG PERFORATED AT 750' AND PUMPED 120 SX NO BLOW-TIED ONTO BACKSIDE

MIXED 25 SX CEMENT PRESSURED TO 500# AND HELD. PUMPED ANOTHER 25 SX CEMENT DOWN CASING

SHUT IN WITH 100#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Michael J. Maier (TECHNICIAN) FORM CP-2/3

1-15-99  
60542