

1060215

TO: STATE CORPORATION COMMISSION

API NUMBER 15-135-20,192-0000
C SW NW SEC. 13, T 20 S, R 23 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MARANVILLE "B" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY NESS 141.15

OPERATOR LICENSE # 9067 7/27 WELL TOTAL DEPTH 4343 FEET

OPERATOR: DAMAR RESOURCES, INC. PRODUCTION CSG: SIZE 5 1/2" @ 4333' WITH 150 SX

NAME AND PO BOX 70 SURFACE CASING: SIZE 8 5/8" @ 282' WITH 185 SX

ADDRESS HAYS, KS 67601

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR HEMBREE WELL SERVICE, INC LICENSE NUMBER 32066

ADDRESS PO BOX 458, NESS CITY, KS 67560-0458

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 27 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM _____

(COMPANY NAME) HEMBREE WELL SERVICE (PHONE) 785-798-3408

WERE: PERFS AT 4232-40. SQUEEZED @ 800 W/325 SX, 950 W/150 SX, 2420' W/150 SX, 2850 W/200 SX, 3420 W/200 SX

RUN TUBING TO 4295' AND MIX 35 SX CEMENT & 200# HULLS. DISPLACED TO BOTTOM. PULLED TUBING TO 1450'. PULLED TUBING TO 1450' AND PUMPED CEMENT UNTIL IT CIRCULATED, USED 130 SX CEMENT AND CIRCULATED TO TOP. PULLED TUBING AND TOPPED OFF WITH 75 SX CEMENT. TIED ONTO BACK-SIDE AND PUMPED 10 SX CEMENT AND PRESSURED TO 500# AND HELD.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 5:30 PM DAY: 27 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT _____

RUN TUBING TO 4295' AND MIXED 35 SX CEMENT AND 200# HULLS. DISPLACED TO BOTTOM. PULLED TUBING TO 1450'. PULLED TUBING TO 1450' & PUMPED CEMENT UNTIL CIRCULATED. USED 130 SX CEMENT & CIRCULATED TO TOP. PULLED TUBING & TOPPED OFF WITH 75 SX CEMENT. TIED ONTO BACK-SIDE AND PUMPED 10 SX CEMENT. PRESSURED TO 500# AND HELD.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED. STATE CORPORATION COMMISSION
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING:

INVOICED
DATE 8/10/00
INV. NO. 1060330

SIGNED Michael J Maier
(TECHNICIAN)

RECEIVED
AUG 4 2000
FORM CONSERVATION DIVISION
Wichita, Kansas