

To: 1 071035 3-18  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-20,418-0000 146  
SW NE, SEC. 13, T. 20 S, R. 23 W/EX  
3300 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 9067

Lease Name Betz "A" Well # 2  
County Ness 141.08

Operator: DaMar Resources, Inc.  
Name:  
Address P.O. Box 70  
Hays, KS 67601

Well Total Depth 4341 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 329

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor DaMar Resources, Inc. License Number 9067  
Address P.O. Box 70, Hays, KS 67601

Company to plug at: Hour: 2 p.m. Day: 18 Month: 3 Year: 19 92

Plugging proposal received from Curtis Longpine  
(company name) DaMar Resources (phone) 913-625-0020

were: 5 1/2" at 4337' w/125 sx cement, squeezed at 800' w/300 sx cement, PBDT 4100',  
Perfs at 4233-39'

1st plug set CIBP at 4100',  
2nd plug pump 700 lbs. hulls in 300 sx cement down 5 1/2".  
Check backside.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 18 Month: 3 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4100',  
2nd plug pumped 700 lbs. hulls in 300 sx cement down 5 1/2". Maximum pressure 20 psi and shut in  
0 psi.

Backside would not take.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 4-7-92  
INV. NO. 34878

Signed Dan Goodrow  
(TECHNICIAN)

RECEIVED  
APR 2 1992

15-135-20418-0000

# GREAT GUNS

R/A Loy

FILING NO.	COMPANY	PALOMINO PETROLEUM	
	WELL	BETZ "A" NO. 2 (TWIN)	
	FIELD	RIVERSIDE	
	COUNTY	NESS	STATE KANSAS
LOCATION:		C 6W NE	OTHER SERVICES:
SEC 13		TWP 20S	RGE 23W

PERMANENT DATUM:	GROUND LEVEL	ELEV. 2222'	ELEV. K.B. 2227'
LOG MEASURED FROM	KELLY BUSHING 5 FT. ABOVE PERM. DATUM	D.F. 2224'	G.I. 2222'
DRILLING MEASURED FROM	KELLY BUSHING		

DATE	3-10-71	3-10-71	STATE	<b>RECEIVED</b> CORPORATION COMMISSION <b>MAR - 6 1992</b> CONSERVATION DIVISION Wichita, Kansas
RUN NO.	ONE	ONE		
TYPE LOG	GAMMA	NEUTRON		
DEPTH-DRILLER	4289'	4289'		
DEPTH-LOGGER	4289'	4289'		
BOTTOM LOGGED INTERVAL	4280'	4289'		
TOP LOGGED INTERVAL	3550'			
TYPE FLUID IN HOLE	WATER			
SALINITY, PPM CL				
DENSITY				
LEVEL	2950'			
MAX. REC. TEMP., DEG F.				
OPERATING RIG TIME	ONE HOUR			
RECORDED BY	ROBBEN			
WITNESSED BY	MR. WATSON			

RUN NO.	BORE-HOLE RECORD			CASING RECORD			
	BIT	FROM	TO	SIZE	WGT.	FROM	TO
12	000	250'		2 5/8	29	000	240'
7 7/8	250'	4333'		5 1/2	14	000	4227'

EQUIPMENT DATA

Neutron