

To: 1 060062  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

10-9 API NUMBER 15-135-20,342-0000  
C NE SW, SEC. 13, T 20 S, R 23 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Operator: DaMar Resources, Inc.  
Name & Address P.O. Box 70  
Hays, KS 67601

1980 feet from S section line

3300 feet from E section line

Lease Name Maranville A Well # 1

County Ness 140.82

Well Total Depth 4333 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: 12:30 p.m. Day: 9 Month: 10 Year: 19 97

Plugging proposal received from Curtis Longpine

(company name) DaMar Resources, Inc. (phone) 785-625-0020

were: 5 1/2" at 4314' w/125 sx cement, Perfs at 4220-26', Open hole 4314-4333', 5 1/2" squeezed w/240 sx cement 800-31'

1st plug fill 5 1/2" casing through tubing from top to bottom with cement.

2nd plug check backside.

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:30 p.m. Day: 9 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug ran tubing to bottom, circulated cement and hulls to bottom

using 300 sx cement, topped off. Used 60/40 Pozmix 6% gel with 1000 lbs. hulls mixed in.

2nd plug hooked onto casing and pumped 30 sx cement. Pressured to 500# and held.

3rd plug tied onto backside, pumped 10 sx cement, pressured to 500# and held.

Remarks: Cemented by Allied. No casing recovery.

(if additional description is necessary, use BACK of this form.)

(did / ~~XXXXXX~~) observe this plugging.

DATE OCT 23 1997

INV. NO. 49260

Signed Michael Maier (TECHNICIAN)

RECEIVED  
KANSAS CORP  
OCT 21 11 24 AM '97