

1080250

TO:
STATE CORPORATION COMMISSION

6-9

API NUMBER 15-083-20,293 071 00-01
SW SW NW SEC. 12, T 16 S, R 43 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM NORTH SECTION LINE
WICHITA STATE OFFICE BLDG., 130 S. MARKET 340 FEET FROM WEST SECTION LINE
WICHITA, KANSAS 67202 LEASE NAME ROSENBERG A WELL # 1
TECHNICIAN'S PLUGGING REPORT COUNTY GREELEY 17/77
OPERATOR LICENSE # 3273 WELL TOTAL DEPTH 5285 FEET
OPERATOR: HERMAN L. LOEB PRODUCTION CSG: SIZE 4 1/2" @ 5285' WITH 250SX
NAME AND PO BOX 524 SURFACE CASING: SIZE 8 5/8" @ 503' WITH 250SX
ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL E-26,799 D/A OTHER WELL AS HEREINAFTER INDICATED PLUGGING CONTRACTOR KEY ROCKY MOUNTAIN WELL SERVICE LICENSE NUMBER 5866ADDRESS PO BOX 69, CHEYENNE WELLS, CO 82601COMPANY TO PLUG AT: HOUR: 11:15 AM DAY: 09 MONTH: 06 YEAR: 1999PLUGGING PROPOSAL RECEIVED FROM M.L. COX(COMPANY NAME) KEY ROCKY MOUNTAIN WELL SERVICE (PHONE) 307-237-7959

WERE: PERFS AT 5130-46 (MORROW) 1800' & 1000'. 2ND STAGE SQUEEZE PERFS W/350 SX CEMENT
SET CIBP @ 4777' WITH 2 SX CEMENT ON TOP. SET CIBP @ 1935'. RAN TUBING IN HOLE TO 1915'.
ALLIED CEMENTING PUMPED 100 SX CEMENT CIRCULATED TO SURFACE, PULLED TUBING TO 600' PUMPED
15 SX CEMENT, PULLED TUBING OUT OF HOLE TOPPED OFF WITH 10 SX CEMENT. PUMPED DOWN 8 5/8" X
4 1/2" ANNULUS 10 SX CEMENT. PRESSURED UP TO 500#.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBEPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 09 MONTH: 06 YEAR: 1999ACTUAL PLUGGING REPORT

SET CIBP @ 4777' WITH 2 SX CEMENT ON TOP. SET CIBP @ 1735'. RAN TUBING IN HOLE TO 1915'.
ALLIED CEMENTING PUMPED 100 SX CEMENT CIRCULATED TO SURFACE. PULLED TUBING TO 600' PUMPED
15 SX CEMENT. PULLED TUBING OUT OF HOLE TOPPED OFF WITH 10 SX CEMENT. PUMPED DOWN 8 5/8" X
4 1/2" ANNULUS 10 SX CEMENT. PRESSURED UP TO 500#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)
I (DID) OBSERVE THIS PLUGGING.

DATE 6-21-99

SIGNED

Kevin D. Strube
(TECHNICIAN)

FORM CP-2/3

INV. NO. 61081