

1080270

TO: STATE CORPORATION COMMISSION

9-27

API NUMBER 15-071-20,336-00-01
SE NW NE SEC. 12, T 16 S, R 43 W

CONSERVATION DIVISION - PLUGGING SECTION ~~4290~~ ^S FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1550 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME OTIS WELL # 7

TECHNICIAN'S PLUGGING REPORT COUNTY GREELEY

OPERATOR LICENSE # 3273 WELL TOTAL DEPTH 5300 FEET

OPERATOR: HERMAN L. LOEB PRODUCTION CSG: SIZE 4 1/2" @ 5300' WITH 200 SX

NAME AND PO BOX 524 SURFACE CASING: SIZE 8 5/8" @ 464' WITH 225 SX

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL GAS WELL INPUT WELL E-26,799 SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MULL DRILLING COMPANY INC. LICENSE NUMBER 5144

ADDRESS PO BOX 2758 WICHITA, KS 67201-2758

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 27 MONTH: 09 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM M.L. COX

(COMPANY NAME) MULL DRILLING (PHONE) 316-264-6366

WERE: PERFS AT 5140-73 DV @ 1776' W/150 SX LITE & PERF AT 1000' W/ 180 SX LITE.

SET CIBP @ 5100 WITH 2 SX CEMENT. SET CIBP AT 2000'. RAN TUBING IN HOLE TO 1980'.

PUMPED 105 SX CEMENT CIRCULATED TO SURFACE. PULLED TUBING UP TO 600' PUMPED 10 SX CEMENT.

PULLED TUBING OUT OF HOLE. TOPPED OFF WITH 7 SX CEMENT. PUMPED DOWN 8 5/8 X 4 1/2 ANNULUS.

PRESSURED UP TO 500#.

INVOICED

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

INV. NO. 60746

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:40 AM DAY: 27 MONTH: 09 YEAR: 1999

ACTUAL PLUGGING REPORT

PEAK WIRELINE SET CIBP AT 5100' WITH 2 SX CEMENT. SET CIBP AT 2000'. RAN TUBING IN HOLE

TO 1980'. ALLIED PUMPED 105 SX CEMENT CIRCULATED TO SURFACE. PULLED TUBING UP TO 600'

PUMPED 10 SX CEMENT. PULLED TUBING OUT OF HOLE. TOPPED OFF WITH 7 SX CEMENT. PUMPED DOWN

8 5/8 X 4 1/2 ANNULUS. PRESSURED UP TO 500#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin D. Strube CONSERVATION DIVISION (TECHNICIAN) FORM CW 12/13/93 Kansas

RECEIVED STATE CORPORATION COMMISSION 10-13-99 OCT 13 1999