

1080255

TO: 7-13
STATE CORPORATION COMMISSIONAPI NUMBER 15-071-20,326-00-01
NE NE NE SEC. 12, T 16 S, R 43 WCONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINEWICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME OTIS WELL # 5

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEYOPERATOR LICENSE # 3273WELL TOTAL DEPTH 5300 172.25 FEETOPERATOR: HERMAN L. LOEB PRODUCTION CSG: SIZE 4 1/2" @ 5294' WITH 200 SXNAME AND PO BOX 524 SURFACE CASING: SIZE 8 5/8" @ 471' WITH 235 SXADDRESS LAWRENCEVILLE, IL 62439ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A OTHER WELL AS HEREINAFTER INDICATED PLUGGING CONTRACTOR KEY ROCKY MOUNTAIN WELL SERVICE LICENSE NUMBER 5866ADDRESS PO BOX 69, CHEYENNE WELLS, CO 82601COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 13 MONTH: 07 YEAR: 1999PLUGGING PROPOSAL RECEIVED FROM M.L. COX(COMPANY NAME) KEY ROCKY MOUNTAIN WELL SERVICE (PHONE) 307-237-7959WERE: PERFS AT 5135-78, DV @ 1748' WITH 330 SX CEMENT, TOP CEMENT AT 1745'.SET CIBP @ 5100' WITH 2 SX CEMENT ON TOP. RUN TUBING IN HOLE WITH 4 1/2 PACKER SET AT 2000'.PRESSURED UP TO 300# AND HELD. PULLED TUBING OUT OF HOLE. SET CIBP @ 1950'. PERFORATED AT1600'. RAN TUBING IN HOLE OPEN ENDED TO 1915'. PUMPED 100 SX CEMENT CIRCULATED TO SURFACE.PULLED TUBING TO 600'. PUMP 15 SX CEMENT. PULL TUBING OUT OF HOLE. PUMP DOWN 4 1/2 SQUEEZED85 SX CEMENT. MAXIMUM PSI @ 1000#. SHUT IN @ 200#. PUMPED DOWN 8 5/8 X 4 1/2 ANNULUS 100 SX CEMENTMAXIMUM PSI @ 200#. SHUT IN AT 100#.PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBEPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 13 MONTH: 07 YEAR: 1999

ACTUAL PLUGGING REPORT

SEE ATTACHED PAGE.

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1999

7-28-99

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.DATE AUG 12 1999 (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)
(DID) OBSERVE THIS PLUGGING.SIGNED Kevin D. Strube

(TECHNICIAN)

FORM CP-2/3

INV. NO. 60085

(2)

ACTUAL PLUGGING REPORT FOR OTIS #5 GREELEY COUNTY

Peak Wireline set CIBP @ 5100' with 2 sx cement on top. Key Rocky Mountain ran tubing in hole with 4½ packer set at 2000'. Pressured up to 300# and held. Pulled tubing out of hole. Peak Wireline set CIBP @ 1950'. Perforated at 1600'. Ran tubing in hole open ended to 1915'. Allied pumped 100 sx cement. Circulated to surface. Pulled tubing to 600'. Allied pumped 15 sx cement. Pulled tubing out of hole. Pumped down 4½ squeezed 85 sx cement. Maximum psi @ 1000#. Shut in @ 200#. Pumped down 8⅝ x 5½ annulus 100 sx cement. Maximum psi @ 200#. Shut in @ 100#.

RECEIVED
STATE NATURAL RESOURCES COMMISSION

JUL 28 1999

CONSERVATION DIVISION
Wichita, Kansas