

TO: 1080258

8-25 API NUMBER NA 15-071-20311-00-00  
NE NW SW SEC. 12, T 16 S, R 43 W

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM WEST SECTION LINE  
WICHITA, KANSAS 67202 LEASE NAME GARRISON A WELL # 6

TECHNICIAN'S PLUGGING REPORT COUNTY GREELEY

OPERATOR LICENSE # 3273 WELL TOTAL DEPTH 5300 172.25 FEET

OPERATOR: HERMAN L. LOEB PRODUCTION CSG: SIZE 4 1/2" @ 5300' WITH 200 SX

NAME AND PO BOX 524 SURFACE CASING: SIZE 8 5/8" @ 446' WITH 250 SX

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MULL DRILLING COMPANY INC LICENSE NUMBER 5144

ADDRESS PO BOX 2758 WICHITA, KS 67201-2758

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 25 MONTH: 08 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM M.L. COX

(COMPANY NAME) MULL DRILLING COMPANY INC. (PHONE) 316-264-6366

WERE: PERFS AT 5160-70. 2nd stage cement sleeve at 1760' never cemented

SET CIBP AT 5100', SPOT 2 SX CEMENT ON PLUG WITH BAILER. RUN TUBING & PACKER TO 2000', SET PACKER AND LOAD ANNULUS WITH WATER. PRESSURE TEST TO 300#. PULL TUBING AND PACKER. SET CIBP AT 2000' IF THERE ARE NO CASING LEAKS ABOVE 2000'. RUN TUBING.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 25 MONTH: 08 YEAR: 1999

ACTUAL PLUGGING REPORT

PEAK WIRE LINE SET CIBP @ 5100' WITH 2 SX CEMENT ON TOP. ON 8-24-99 RAN TUBING AND 4 1/2" PACKER TO 2000' PRESSURED UP TO 300#. PULLED TUBING & PACKER. SET CIBP @ 1998'. PERFORATED AT 1950'. RAN TUBING BACK IN HOLE TO 1957'. ON 8-25-99 ALLIED PUMPED 110 SX CEMENT PULLED TUBING TO 600' PUMPED 30 SX CEMENT. PULLED TUBING OUT OF HOLE PUMP DOWN 4 1/2" 60 SX CEMENT. MAXIMUM PRESSURE AT 500#. SHUT IN WITH 100#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 100 SX CEMENT. SHUT IN AT 50#.

RECEIVED  
STATE CORPORATION COMMISSION  
9-7-99  
SEP 7 1999

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 9/7/99 SIGNED Kevin P. Strube (TECHNICIAN) WICHITA STATE CORPORATION COMMISSION FORM CP-2/3

INV. NO. 60523

INVOICED